

35.21 Schedules A and B

Schedule A - Description Of Interconnection Facilities

The NYISO – PJM Coordination Agreement covers the PJM – NYISO *Interconnection Facilities* under the *Operational Control* of the NYISO and PJM. For *Operational Control* purposes, the point of demarcation for each of the *Interconnection Facilities* listed below is the point at which each *Interconnection Facility* crosses the PJM-New York State boundary, except as noted below.

The PJM-NYISO *Interconnection* contains twenty-three (23) alternating current (“AC”) *Interconnection Facilities*, seven (7) of which form one (1) AC pseudo-tie¹; and further contains one (1) HVDC *Interconnection Facility* as well as one (1) *Variable Frequency Transformer (VFT)*. These are tabulated below:

NY/PJM AC *Interconnection Facilities*:

PJM	NYISO	Designated	(kV)	Common Meter Point
Branchburg	Ramapo	5018	500	Ramapo
Cresskill	Sparkill	751	69	Cresskill
E. Sayre	N. Waverly	956	115	E. Sayre
E. Towanda	Hillside	70	230	Hillside
Erie East	South Ripley	69	230	South Ripley
Harings Corners	Corporate Drive	703	138	Harings
Harings Corners	Pearl River	45	34	Harings
Harings Corners	W. Nyack	701	69	Harings
Homer City	Watercure	30	345	Homer
Homer City	Stolle Road	37	345	Homer
Hudson	Farragut	C3403	345	Farragut
Hudson	Farragut	B3402	345	Farragut
Linden	Goethals	A2253	230	Goethals
Linden VFT	Linden Cogen	VFT	345	Linden VFT
Montvale	Pearl River	491	69	Montvale
Montvale	Blue Hill	44	69	Montvale
Montvale	Blue Hill	43	69	Montvale
S. Mahwah	Hilburn	65	69	S. Mahwah
S. Mahwah	S. Mahwah	BK 258	138/345	S. Mahwah
S. Mahwah	Ramapo	51	138	S. Mahwah
Waldwick	S. Mahwah	J3410	345	Waldwick
Waldwick	S. Mahwah	K3411	345	Waldwick
Tiffany	Goudey	952	115	Goudey
Warren	Falconer	171	115	Warren
RECO	NYISO	AC Pseudo-Tie	Various	O&R EMS

¹ WEQ-007 “Inadvertent Interchange Payback Standards,” North American Energy Standards Board (NAESB), on-line at www.naesb.org.

Sayerville Newbridge HVDC-Tie 500 Newbridge

Schedule B - Other Existing Agreements:

- 1.0 Lake Erie Emergency Redispatch (LEER)
- 2.0 RAMAPO PHASE ANGLE REGULATOR OPERATING PROCEDURE prepared by the NYPP/PJM Circulation Study Operating Committee.
- ~~3.0 Operating Protocol for the Implementation of Commission Opinion No. 476, Docket No. EL02-23-000 (Phase II), New York Independent System Operator, Inc., FERC Electric Tariff, Original Vol. No. 2, Attachment M-1.~~
- 34.0 Northeastern ISO/RTO Coordination of Planning Protocol
- 45.0 Inter Control Area Transaction Agreement.
- 56.0 Procedures to Protect for Loss of Phase II Imports (effective January 16, 2007, pursuant to Order issued January 12, 2007, in FERC Docket No. ER07-231-000).
- 67.0 Joint Emergency Operating Protocol dated September 10, 2009, among PJM Interconnection, L.L.C., New York Independent System Operator, Inc., and Linden VFT, LLC (Filed by PJM on October 1, 2009, in FERC Docket No. ER09-996-000).